



EX. CURB INLET  
RIM: 11.29  
THROAT: 10.30  
INV EL 6.09 24" (SE)  
INV EL 5.99 24" (NE)  
INV EL 6.33 24" (W)

FND CAPPED  
IRON ROD  
#4882

EX. BUBBLE UP STRUCTURE  
RIM: 6.06  
BTM: 1.52  
FULL OF WATER

OUTFALL STRUCTURE  
FDOT TYPE E BOX  
TOP ELEV = 9.50  
INV ELEV (24") = 6.00  
BOTTOM ELEV = 6.00

EX. RIP-RAP  
5' WIDE

EX. CONCRETE OVERFLOW STRUCTURE  
OVERFLOW EL: 9.81

FDOT MITERED END SECTION  
24" INV = 5.00  
PROVIDE CONCRETE RIP-RAP  
AT INVERT AS SHOWN

- LEGEND**
- DENOTES ELEC PEDISTAL
  - ☆ DENOTES LIGHT POLE
  - DENOTES IRON ROD
  - ▨ DENOTES CONCRETE
  - BTM DENOTES BOTTOM
  - EL DENOTES ELEVATION
  - RCP DENOTES REINFORCED CONCRETE PIPE.
  - INV DENOTES INVERT
  - DENOTES CHAIN-LINK FENCE
  - DENOTES TREELINE
  - DENOTES WOODEN FENCE

**GENERAL NOTES:**

1. THE CONTRACTOR SHALL NOTIFY THE CITY OF GULF BREEZE AT LEAST 72 HOURS PRIOR TO COMMENCEMENT OF CONSTRUCTION.
2. NO DEVIATIONS FROM THE PROJECT PLANS OR SPECIFICATIONS ARE ALLOWED WITHOUT PRIOR WRITTEN APPROVAL FROM THE CITY OF GULF BREEZE.
3. THE CONTRACTOR IS ADVISED TO VISIT THE SITE AND FAMILIARIZE HIMSELF WITH THE EXISTING CONDITIONS PRIOR TO BIDDING AND/OR CONSTRUCTION.
4. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT ALL REQUIRED PERMITS ARE OBTAINED AND IN HAND PRIOR TO CONSTRUCTION. NO CONSTRUCTION OR FABRICATION OF ANY ITEM SHALL BEGIN UNTIL THE CONTRACTOR HAS RECEIVED ALL PLANS AND OTHER DOCUMENTATION FROM ALL OF THE PERMITTING AND ANY OTHER REGULATORY AUTHORITIES. ANY PENALTIES, STOP WORK ORDERS OR ADDITIONAL WORK RESULTING FROM THE CONTRACTOR BEING IN VIOLATION OF THE REQUIREMENTS ABOVE SHALL BE FULLY BORNE BY THE CONTRACTOR.
5. SOD ALL DISTURBED AREAS OF BOTH RETENTION POND SLOPES WITH COMMON BERMUDA.
6. THE CONTRACTOR SHALL VERIFY SIZE, LOCATION AND DEPTH OF ALL UTILITIES PRIOR TO CONSTRUCTION. UTILITIES SHOWN ARE APPROXIMATE IN LOCATION. THE CONTRACTOR AGREES TO BE COMPLETELY RESPONSIBLE FOR ANY DAMAGES WHICH OCCUR DUE TO HIS FAILURE TO ADEQUATELY LOCATE AND PROTECT EXISTING UTILITIES.
7. CONTRACTOR SHALL NOTIFY SUNSHINE STATE ONE CALL 72 HOURS PRIOR TO DIGGING IN THE RIGHTS-OF-WAY. 1-800-432-4770.
8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY EROSION AND SEDIMENTATION MEASURES THAT MAY OCCUR AS A RESULT OF THIS PROJECT.

**jhi jehle-halstead, inc.**  
Civil Engineering and Surveying  
5414 Highway 90 • Milton, Florida 32571  
(850) 994-9503 • Fax (850) 994-9504  
www.jhi-halstead.com  
Certificate of Authorization No. 0000899  
Surveying License Number 02965

PLANTATION HILL  
RETENTION POND  
GULF BREEZE, FLORIDA  
CITY OF GULF BREEZE

OUTFALL PLAN

Valid only with  
embossed seal

Revisions	
Date	Description

Designed By: **MGN**  
Drawn By: **MGN**  
Checked By: **DPJ**  
Job No.: **140050**  
Date: **10-9-14**  
Scale: **1" = 10'**  
Sheet No.: **C-1**

**C-1**